123 Washington Street Columbus, Indiana 47201 Phone: (812) 376-2550 Fax: (812) 376-2643





STAFF REPORT

CITY OF COLUMBUS PLAN COMMISSION (July 8, 2015 Meeting)

Docket No. / Project Title: PUDF-16-04 (White River Dental)

Staff: Ashley Klingler

Applicant: **AWS Properties LLC**

Property Size: +/- 1.74 Acres

PUD (Planned Unit Development) **Current Zoning:**

Location: The property is located at the north east corner of Johnson Boulevard

and Merchants Mile.

Background Summary:

AWS Properties LLC is requesting a modification to a Final PUD Plan for White River Dental. The request includes updates to signage and landscaping.

Key Issue Summary:

The following key issue(s) should be resolved through the consideration of this application:

- 1. Is the proposed Final PUD consistent with the Preliminary PUD?
- 2. Does the proposed landscaping meet the intent of the regulations by providing fewer shrubs but more trees in the parking lot frontage landscaping area?
- 3. Does the proposed landscaping meet the intent of the regulations by providing enough plantings in a smaller area in the parking lot interior landscaping area?
- 4. Is the north side of the building/property screened appropriately?

Staff Recommendation:

Approval, with the following conditions:

- 1. Landscaping (6 shrubs) shall be required at the base of the 25 foot sign.
- 2. The north side of the property shall have landscaping. The trees along the pond are to be retained, or some landscaping shall be moved to the north side of the building from other landscape areas that have a large amount of landscaping.

Current Property Information:		
Land Use:	Undeveloped	
Site Features:	Grassy lawn, trees, edge of detention pond	

Flood Hazards:	As shown on Flood Insurance Rate Map (FIRM) 18005C0129E, effective December 9, 2014, the northern portion of the property is located in Flood Zone AE, more commonly called the 100-year floodway fringe. The majority of the rest of the property is located in the Flood Zone X (Shaded), more commonly called the 500-year floodway fringe.	
Vehicle Access:	Johnson Boulevard (Local, Commercial, Suburban) Merchants Mile (Local, Commercial, Suburban)	

Surrounding Zoning and Land Use:				
	Zoning:	Land Use:		
North:	CR (Commercial: Regional)	Detention pond, Sleep Inn farther north, Centra to the north-east		
South:	PUD (Planned Unit Development)	Menard's		
East:	PUD (Planned Unit Development)	Undeveloped		
West:	PUD (Planned Unit Development)	Undeveloped, I-Hop to the north-west		

Proposal / General Standards Summary:

The following table compares the proposed features of the development with the standards established by the Preliminary PUD and in a comparable zoning district. A check mark indicates that the proposal is consistent with these general standards. All project features must follow the Preliminary PUD. With additions to these requirements are subject to the discretion and approval of the Plan Commission.

Criterion / Status		Summary of PUD Proposal	Summary of Preliminary PUD Requirements	Summary of Zoning Ordinance Requirements
Landscaping:	X	Area #1 Parking Lot Public Street Frontage: 11 large trees, 2 medium trees, 3 small trees, 74 shrubs. Area #2 Parking Lot Interior: Island/Peninsula: 1825 total sq. ft. Some peninsulas are only 120 sq.ft. Plantings: 6 trees and 44 shrubs	Landscaping for the PUD shall at a minimum meet the requirements of Chapter 17.43 of the Zoning Ordinance for B-5 commercial development and also at the Plan Commission's discretion. Final PUD plans for all buildings on the north side of Merchants Mile shall include landscaping and architectural treatment along both north and south sides of buildings.	Area #1 Parking Lot Public Street Frontage: 10 large trees or 12.5 medium trees, and 75 shrubs Area #2 Parking Lot Interior: Island/Peninsula: 1862.35 sq. ft. Islands must be at least 300 sq.ft. and peninsulas must be at least 150 sq.ft. Plantings: 6 trees and 36 shrubs

		Area #3 Front Setback: 37.5 points		Area #3 Front Setback: 32.4 points
		Area #4 Lot Interior: Phase 1-3= 157.5 points 157.5 points within 15 ft. of the building.		Area #4 Lot Interior: Phase 1= 86 points (21 points of which, must be within 15 ft. of the building)
		(Each phase has the same number of points; the plants are just relocated as the building expands.)		Phase 2= 101 points (25 points of which, must be within 15 ft. of the building) Phase 3= 115 points (29 points of which, must be within 15 ft. of the building)
		Area #5 Freestanding Signs Exceeding 6 ft: Sign #1 (Merchants Mile): 6 shrubs		Area #5 Freestanding Signs Exceeding 6 ft: 6 shrubs within 5 feet from the base of the sign.
		Sign #2 (Johnson Boulevard): No shrubs		
Street Trees:	✓	Johnson Boulevard: no trees proposed	Johnson Boulevard: no trees required	None.
		Merchants Mile: 7 Japanese Zelkova trees	Merchants Mile: 7 Japanese Zelkova trees required	
Signage:	√	Freestanding: Two Signs Sign #1 (Merchants Mile): Total Sign Area: 14.37 sq.ft. Total Height: 6 ft. Material: Aluminum Sign #2 (Johnson Boulevard): Total Sign Area: 150 sq.ft. Total Height: 25 ft. Material: Aluminum	Signs shall be generally consistent with the CR Commercial: Regional Center) Zoning District (or any similarly intended zoning district as may be adopted in the future). The Plan Commission shall not be bound exclusively to the CR zoning district standards and may further limit and/or permit signs. All permanent signs shall be designed with appearance in mind and shall be consistent and compatible with the overall design characteristics of the structure(s) on each lot.	Freestanding: Max number per street frontage: 1 (2 allowed on this site). Max Area: 150 square feet. Max Height: 25 feet.

Changeable Copy:
Sign #1 (Merchants Mile):
Non-changeable portion:
100%

<u>Sign #2 (Johnson</u> <u>Boulevard):</u> Non-changeable portion: 96 sq. ft.

Changeable portion proposed: 54 sq.ft. (72%)

Wall:

Two signs, each 58 sq.ft. in area (4 feet tall by 14.5 feet wide). Totaling 116 sq.ft.

Permanent freestanding signs shall make use of supports and other design elements that are consistent and compatible with those used on the structure(s) on the same lot on which they are located.

Changeable Copy: The area of the changeable copy elements shall not exceed 75% of the area of the non-changeable elements.

Wall:

Max number per street frontage per use: 3. (6 allowed on this site) Maximum area, whichever is greater: 15% of wall area or 350 sq.ft. (350 for this site)

Interdepartmental Review:		
City Engineering:	No outstanding comments.	
Fire Department:	No outstanding comments.	
Code Enforcement:	No outstanding comments.	
Flood Plain Administrator:	No outstanding comments.	

History of this Location:

The relevant history of this property includes the following:

- White River Dental received Final PUD approval July 8th, 2015 (case number PUDF-15-08).
- On September 15, 2015 the City Council signed an Ordinance updating the signage standards in the Columbus Crossing PUD to give more discretion to the Plan Commission when approving signage, and to use the requirements for the CR (Commercial: Regional) zoning district as a guide for signage in the PUD (case number PUD-15-09).

Comprehensive Plan Consideration(s):

The Future Land Use Map indicates the future use of this property as commercial.

The following Comprehensive Plan goal(s) and/or policy(ies) apply to this application:

 POLICY A-2-16: Promote simple, objective design standards (not an architectural review committee) for commercial, industrial, and institutional development. Because the appearance of the community is important, the City needs to promote design standards that will lead to attractive

- development. These standards might include such things as variations in roof lines or building facades, requirements for windows, or standards for the placement of buildings on their lots.
- **POLICY E-2-1:** Encourage development of these corridors in a manner that is visually appealing. Highway corridors greatly impact the appearance of a community. Because community appearance is important to local residents, the city should encourage these corridors to be developed in a manner that enhances community appearance. Elements to be considered include landscaping, screening or outdoor storage and display, appearance of buildings, design of parking areas, and others.
- POLICY E-2-3: Establish objective design standards (not an architectural review committee), to
 encourage development with appropriate landscaping, parking, setbacks, visually appealing
 buildings, and attractive and effective signage. Design standards could include such things as
 requirements for variations in building facades, roof lines, materials, colors, and limitations on
 outside storage.
- **POLICY E-2-10:** Encourage businesses along these corridors to add landscaping. Landscaping adds greatly to the appearance of the community, and it offers environmental, economic, and psychological benefits. Highway corridors are the most visible areas to visitors and local residents alike; therefore, landscaping is particularly important in these areas.
- Policy J-10-1: Create a positive business climate characterized by flexibility. The needs of businesses are continuously changing, and the City needs to have sufficient flexibility in its regulatory system to respond to these changes and to encourage and nurture new businesses.

This property is located in the Western Gateway character area. The following Planning Principle(s) apply to this application: None.

Planning Consideration(s):

The following general site considerations, planning concepts, and other facts should be considered in the review of this application:

1. This request is for modifications to the Final PUD for White River Dental. The updates include alterations to signage and landscaping. In general, the signage is larger than the previous request, and there is overall less landscaping than the previous request. The following tables compare what is currently proposed with the previous approval.

	Sig	nage	
Topic	Proposed	Previous Plan	Change
Number of	2	1	+1
Freestanding			
Signs			
Area of	Sign #1: 14.37 sq.ft.	71.55 sq.ft.	Sign #1: smaller
Freestanding	Sign #2: 150 sq.ft.		Sign #2: larger
Signs			
Number of Wall	2	4	-2
Signs			
Area of Wall	58 sq.ft. each	49.84 sq.ft each	+8.16 sq.ft. each
Signs	(116 total sq.ft.)	(199.36 total sq.ft.)	(-83.36 total sq.ft)

	Landscaping			
Area	Proposed	Previous Plan	Change	
Area #1:	11 large trees, 2 medium	10 large trees, 2	+1 large tree,	
Parking Lot Public Street Frontage	trees, 3 small trees, 74 shrubs.	medium trees, 3 small trees, 63 shrubs	= same number of medium trees, = same number of small trees, + 11 shrubs	

Area #2:	Island/Peninsula: 1825	Island/Peninsula:	- came amount of
			= same amount of
Parking Lot	total sq. ft. Some	1825 total sq. ft.	square footage,
Interior	peninsulas are only 120	Some peninsulas are	= same number of
	sq.ft.	only 120 sq.ft.	trees,
	- 4	,	+5 shrubs
	Plantings: 6 trees and 44 shrubs	Plantings: 6 trees, 39 shrubs	
Area #3: Front	37.5 points	62.5 points	- 25 points (ex: 1 large
Setback			tree or 4 shrubs)
Area #4: Lot	Phase 1-3= 157.5 points	Phase 1= 1175 points	-1017.5 points (ex: 41
Interior	157.5 points within 15 ft. of	(415 points within 15	large trees or 136
	the building.	ft. of the building)	shrubs)
		3,	,
	(Each phase has the same	Phase 2= 1160 points	
	number of points; the	(490 points within 15	
	plants are just relocated as	ft. of the building)	
	the building expands.)	55 5 3 1 3 1 1 9)	
		Phase 3= 1135 points	
		(590 points within 15	
		ft. of the building)	
i .		it. of the building)	

- 2. On September 15, 2015 the City Council signed an Ordinance updating the signage standards in the Columbus Crossing PUD to give more discretion to the Plan Commission when approving signage, and to use the requirements for the CR (Commercial: Regional) zoning district as a guide for signage in the PUD. The proposed signage is consistent with the CR signage requirements. The Plan Commission does have the discretion to approve or deny the signage.
- 3. When comparing the landscaping to the CR (Commercial: Reginal) zoning district requirements, the landscaping under the signs does not comply. The larger sign (25 foot tall) requires landscaping at the base of the sign. Section 8.1(5) of the Zoning Ordinance states that signs over 6 feet need landscaping at the base of the sign. The 40 points required is approximately 6 shrubs within 5 feet from the base of the sign. It is important to note that, under the CR requirements, the shrubs required for the sign cannot double count toward any other landscape area. The current plan has perennials under the 25 foot sign. Even though it is not required, the smaller sign does have 6 shrubs below it. The Plan Commission does have the discretion to require these shrubs below the signs.
- 4. When comparing this request to the CR (Commercial: Reginal) zoning district requirements, the applicant has provided enough over-all points for the landscaping requirements. The landscaping, however, is not in the appropriate detailed areas as designated by the Zoning Ordinance. The lot interior, and front setback areas have plenty of "landscape points", while the, parking lot frontage, parking lot interior, and signage landscaping do not meet the requirements. The parking lot frontage is deficient one shrub, but the plan has more trees than required. The parking lot interior has enough plants, but the square footage of the planting area is technically too small. The Plan Commission does have the discretion to approve or deny the landscaping plan.
- 5. The previous landscaping plan showed 12 shrubs along the northern foundation of the building. There were also 9 trees and 15 shrubs along the northern portion of the property. These plants helped screen the trash enclosure and parking areas from view from those traveling south along Johnson Boulevard. The proposed landscaping plan does not have any landscaping on the northern portion of the property. The preliminary PUD states that for all buildings on the north side of Merchants Mile, landscaping and architectural treatment shall be along both north and south sides of buildings. The intent behind this is to not have a "back" of the building. It is important to note that there are trees surround the retention pond to the north of the subject property. These trees provide a screening for the northern portion of the building to those traveling south along Johnson Boulevard. It would be beneficial to either retain these trees along the pond, or provide plants along the northern portion of the property. When adding new plants

along the north side of the building, the applicant can move plants from other areas around the site that "exceed" the requirements. For example, there are plants along the parking lot frontage that exceed the requirements for the CR (Commercial: Regional) zoning district. Some plants from this area could move to the north side of the property.

Decision Criteria:

When considering a request for <u>final PUD</u> approval the Plan Commission and legislative body shall pay reasonable regard to the following, (per Zoning Ordinance Section 5.1(E)):

- 1. The extent to which the proposal is consistent with the approved Preliminary Plan;
- 2. The extent to which the proposal fulfills the requirements and intent of Article 5 of the Zoning Ordinance; and
- 3. The Comprehensive Plan and any other applicable, adopted planning studies or reports.

Plan Commission Options:

In reviewing a request for a <u>final PUD</u> the Plan Commission may (1) approve the request, (2) deny the request, or (3) continue the review to the next Plan Commission meeting. The Plan Commission may request modifications to the proposed detailed PUD.


Columbus – Bartholomew County Planning Department

Planning Unit Development (PUD) Application


Planning Department Use Only:		AI K 0 0 2010
Jurisdiction: X Columbus Bartholomew County	Joint District	A A GI
Docket No.:		BY: TO CIC
Planned Unit Development (PUD) Appl	ication:	
. , , , , , , , , , , , , , , , , , , ,		
Application Type Preliminary PUD Plan	Final PUD Plan & Rezoning	
☐ Minor Modification	☑ Major Modification (a Preliminary o	r Final PUD Revision)
PUD Title: COLUMBUS CROSSING 6 TH REPL	AT LOT DA A	
FOD TILE. COLUMBOS CROSSING 6 REFL	AT LOT 9A-A	
Applicant Information (the person or entity that	will own and/or execute what is proposed)	: \
Name _AWS PROPERTIES LLC	White Kinga Do-	T ()
Name AWSPROPERTIES LLC	2700C March	tax /
Address 2459 W. JONATHAN MOORE P (number) (street)	4 (4)	IN 47201
(street)	(city)	(state) (zip)
Phone No.: <u>812-378-5500</u> Fax No.:	E-mail Address: _	wrdental.columbus@gmail.com
Property Owner Information (the "owner" doe	s not include tenants or contract buyers):	
Name: _AWS PROPERTIES LLC		
Address 2459 W. JONATHAN MOORE P (number) (street)	KE COLUMBUS (city)	IN 47201 (state) (zip)
	0 000 V	
Phone No.: <u>812-378-5500</u> Fax No.:	E-mail Address: _	wrdental.columbus@gmail.com
Property Information:		
Property Size:1.74 acres <u>or</u>	square feet	
Address N/A (number) (street)	(city)	(state) (zip)
-		20 3227
$\underline{\textit{or}}$ General Location (if no address has been assigned	provide a street corner, subdivision lot numbe	r, etc):
LOT 9A-A IN COLUMBUS CROSSING 6 TH REPLA	T IN PLAT BOOK "R", PAGE 349D	
A legal description is attached.		
(a legal description is required for the processing of	all <i><u>Final PUD Plan</u> r</i> equests).	
(refer to Columbus & Bartholomew County Zoning C	rdinance Section 5.3(B) for Preliminary PUD I	Plan requirements and Section 5.4(B) for

Notification Information (list the person to whom all correspondence regarding this application should be directed): Name: <u>E.R. GRAY & ASSOCIATES, PC</u> Address P.O. BOX 1357 COLUMBUS (street) (state) (number) (city) (zip) Phone No.: <u>812-372-</u>7398 Fax No.: 812-372-2175 E-mail Address: er.gray@ergray.com How would you prefer to receive information (please check one): Email Phone Fax Mail Applicant's Signature: The information included in and with this application is completely true and correct to the best of my knowledge and belief. AaronW. Strickland Sole MBR Owner's Signature (the "owner" does not include tenants or contract buyers): I authorize the filing of this application and will allow the Planning Department staff to enter this property for the purpose of analyzing this request. Further, I will allow a public notice sign to be placed and remain on the property until the processing of the request is complete. Sole MBR (Owner's Signature) (Date)

Previously Approved Plan (Case Number PUDF-15-08): Signage





Previously Approved Plan (Case Number PUDF-15-08): Landscaping













IMBUS, OLU

Revisions:

Job Number:

Drawing Name: EXTERIOR SIGNAGE Drawing Number:

S7 QTY (3)
.080 Engineering Grade Reflective Aluminum Mounted on U-Channel post 6'-0" from grade to bottom of sign panel Direct bury installation

S8 QTY (1) .080 Engineering Grade Reflective Aluminum Mounted on U-Channel post 6'-0" from grade to bottom of sign panel Direct bury installation

S9 QTY (1)
.080 Engineering Grade Reflective Aluminum Mounted on U-Channel post 6'-0" from grade to bottom of sign panel Direct bury installation

S10 QTY (2) .080 HIP Reflective Aluminum Mounted on U-Channel post 6'-0" from grade to bottom of sign panel Direct bury installation

TOTAL SIGN PORTION = 150 SQ. FT.

TOTAL ALLOWABLE FOR LED MESSAGE CENTER = 43.8 SQ. FT.

TOTAL NON-CHANGEABLE PORTION = 58.4 SQ. FT.

"WHITE RIVER DENTAL" - Internally illuminated channel letters

LED MESSAGE CENTER = 40.9 SQ. FT.

S5 Fabricate & install QTY (1) Double-sided pylon sign

All aluminum framing and cladding .090 Aluminum skin - paint colors TBD

.040 Aluminum returns - Duranodic Bronze

1/8" White acrylic faces (7328)
1" Duranodic Bronze trimcap

AVL 6500k White LED illumination

LED Electronic Message Center
16MM WatchFire full color display

Ignite Graphics Software - included

Address/Hours Panel - Internally illuminated

Bracket mount to 2" horizontal tube supports


SIDE VIEW SCALE: 1/2"=1'

Mounted flush to topper cabinet

Cabinet Size: 4'-5" x 9'-3"

Viewing Area: 4'-0" x 9'-0"

JOHNSON BLVD SIGN



MERCHANT MILE SIGN

\$6 Fabricate & install QTY (1) Double-sided pylon sign


All aluminum framing and cladding .090 Aluminum skin - paint colors TBD

"WHITE RIVER DENTAL" - Internally routed aluminum faces backlit with 1/8" White acrylic faces (7328)

AVL 6500k White LED illumination

Address/Hours Panel - Internally illuminated 12" Deep aluminum cabinet .090 Aluminum faces with routed copy Backed with 1/8" white acrylic AVL 6500k White LED illumination Bracket mount to 1" horizontal tube supports

Address - Non-illuminated 1/2" Acrylic numbers - paint color (TBD) Flush mount to sign



14" Deep aluminum cabinet .090 Aluminum face with routed copy Backed with 1/8" white acrylic AVL 6500k White LED illumination

> Address - Non-illuminated 1/2" Acrylic numbers - paint color (TBD) Flush mount to sign

ELEVATION SCALE: 1/2"=1'

S4 - East Wall Sign (previously North Wall Sign)


ELEVATION SCALE: 1/4"=1"


Remove & reinstall QTY (1) set of internally illuminated channel letters & logo for

"WHITE RIVER DENTAL" 1/8" Blue acrylic faces .040 Aluminum returns - black 1" Black trimcap White LED illumination Raceway mount to building fascia Repaint raceway to match new building

Raceway colors TBD







ELEVATION SCALE: 1/2"=1'

S1- South Wall Sign Fabricate & install QTY (1) sets of internally illuminated channel letters & logo "WHITE RIVER DENTAL" 1/8" White acrylic faces - (7328) 040 Aluminum returns - black 1" Black trimcap White LED illumination Raceway mount to building fascia

Raceway colors TBD

JOB NUMBER | 11418 JOB NAME | White River Dental SALES REP | Adam Walsh LOCATION Columbus, IN DATE 3-29-16

FILE NAME | whit_II4I8_vIO

This drawing was created to assist you in visualizing our proposal. The original idea herein is the property of ISF INC. Permission to reproduce, copy or use the design or proposal can only be obtained through written agreement with ISF INC. Due to screen calibration and printing capabilities, the colors shown are only to be used as a close representation or final product.


PH | 317.251.1219 ISF TF 888.747.3855 6468 Rucker Road SIGN Indianapolis, IN 46220 WWW.ISFSIGNS.COM SPECIFILISTS


1. TRIM CAP WITH RETAINING SCREW
2. PLEX FACE
3. WHITE L.E.D.
4. ALUMINUM .063" BACKS / .040" RETURN

Some dimenti Edmand & tide district

APR 0 8 2016

5. WALL
6. DISCONNECT SWITCH
7. EXTRUDED ALUMINUM RACEWAY
8. 30 ma TRANSFORMER
9. FASTENERS AS REQUIRED





225 QUERCUS X BICOLOR REGAL PRINCE OAK 2.5" 25 THORNLESS COCKSPUR HAWTHORN CRATAEGUS CRUSGALLI 2.5" 15 0 GR 30 **GOLDEN RAIN TREE** 15 SWEET BAY MAGNOLIA 10 MAGNOLIA VIRGINIANA 6 - 7' CL. 10 15 90 PRUNUS SERRULATA KWANZAN CHERRY 2.5" 6 PRAIRIEFIRE CRABAPPLE 2.5" 10 60 MALUS X 6 25 0 NORWAY SPRUCE 6 - 7' PICEA ABIES 0 ONTARIO BLUE SPRUCE 15 0 PIEA PUNGENS 2.5" WILDFIRE BLACK GUM 25 0 NYSSA SYLVATICA 0 CERCIS CANADENSIS RUBY FALLS REDBUD 10 0 15 90 EXISTING BRADFORD PEAR N/A **PYRUS** DECIDUOUS HOLLY

SHRUBS	SCIENTIFIC NAME	COMMON NAME	SIZE	QUANTITY	POINTS	TOTAL
L	SYRINGA MEYERI	DWARF KOREAN LILAC	18"	24	7.5	180
GV	BUXUS GREEN VELVET	GREEN VELVET BOXWOOD	18"			
GM	BUXUS GREEN MOUNTAIN	GREEN MOUNTAIN BOXWOOD	18"	2	14 1	
T	HYDRANGEA PANICULATA	LATE PANICLE HYDRANGEA	18"	4	7.5	30
НС	CLETHRA ALNIFOLIA	HUMMINGBIRD SUMMERSWEET	18"	7	7.5	52.5
MG	MISCANTHUS SINENSIS	DWARF MAIDEN GRASS	3 GAL	5	7.5	37.5
DK	CARYOPTERIS X CLANDONENSIS	DARK KNIGHT CARYOPTERIS	3 GAL	2	7.5	15
IB	ILEX GLABRA	SHAMROCK INKBERRY	18"	0	7.5	0
ES	HYDRANGEA MACROPHYLLA	ENDLESS SUMMER HYDRANGEA	3 GAL	0	7.5	0
KO	ROSA X KNOCK OUT	KNOCK OUT ROSE	3 GAL	3	7.5	22.5
JB	JUNIPERUS SABINA	BUFFALO JUNIPER	3 GAL	4	7.5	30
SJ	HYPERICUM FRONDOSUM	SUNBURST ST. JOHNSWORT	3 GAL	6	7.5	45
MV	VIBURNUM LANTANA	LANTANA MOHICAN VIBURNUM	18"	5	7.5	37.5
FS	RHUS AROMATICA	GRO-LOW FRAGRANT SUMAC	3 GAL	19		
LL	HYDRANGEA PANICULATA	LIMELIGHT HYDRANGEA	18"	0	7.5	0

PLANT SCHEDULE						
SHRUBS	SCIENTIFIC NAME	COMMON NAME	SIZE	QUANTITY	POINTS	TOTAL
J۷	VIBURNUM X JUDDII	JUDD'S VIBURNUM	18"	12	7.5	90
IH	CORNUS ALBA	IVORY HALO DOGWOOD	18"	13	7.5	97.5
WH	HAMAMELIS VERNALIS	VERNAL WITCH HAZEL	18"	0	7.5	0
LH	ITEA VIRGINICA	LITTLE HENRY SWEETSPIRE	3 GAL	0	7.5	0
OS	CHAENOMELES SPECIOSA	ORANGE STORM QUINCE	3 GAL	16	7.5	120
PERENN!	ALS			-		
BG	HOSTA SIEBOLDIANA	BLUE GIANT HOSTA	1 GAL	0		
SD	LEUCANTHEMUM X SUPERBA	BECKY SHASTA DAISY	1 GAL	8		
PP	HEUCHERA	PLUM PUDDING CORAL BELLS	1 GAL	12		
MN	SALVIA NEMEROSA	MAY NIGHT SALVIA	1 GAL	10		
BES	RUDBECKIA FULGIDA	GOLDSTURM BLACK-EYED SUSAN	1 GAL	0		
KWS	ASTILBE CHINENSIS	VISIONS IN PINK ASTILBE	1 GAL	7		-
ANNUALS	3					
FLO	PETUN	IIAS, GERANIUMS, BEGONIAS, V	/ERBENA, D	USTY MILLER, CO	OLEUS	

Scale:

1/16"=1'-0"

Date:

4.7.2016

Checked By:

Checked By:


AWS Properties COLUMBUS, INDIANA

Revisions:

Job Number:

Drawing Name:
PHASE 2
LANDSCAPE PLAN
Drawing Number:

A015-2



KO

SJ

MV

ROSA X KNOCK OUT

JUNIPERUS SABINA

VIBURNUM LANTANA

RHUS AROMATICA

HYDRANGEA PANICULATA

YPERICUM FRONDOSUM

3 GAL

3 GAL

18"

3 GAL

18"

5

19

KNOCK OUT ROSE

BUFFALO JUNIPER

SUNBURST ST. JOHNSWORT

LANTANA MOHICAN VIBURNUM

GRO-LOW FRAGRANT SUMAC

LIMELIGHT HYDRANGEA

7.5

7.5

7.5

7.5

7.5

22.5

30

45

37.5

MN

BES

KWS

ANNUALS

FLO

SALVIA NEMEROSA

RUDBECKIA FULGIDA

ASTILBE CHINENSIS

MAY NIGHT SALVIA

GOLDSTURM BLACK-EYED SUSAN

VISIONS IN PINK ASTILBE

1 GAL

1 GAL

1 GAL

PETUNIAS, GERANIUMS, BEGONIAS, VERBENA, DUSTY MILLER, COLEUS

10

0

PICEA ABIES

PIEA PUNGENS

NYSSA SYLVATICA

CERCIS CANADENSIS

PYRUS

6 - 7'

6 - 7'

2.5"

NORWAY SPRUCE

ONTARIO BLUE SPRUCE

WILDFIRE BLACK GUM

RUBY FALLS REDBUD

DECIDUOUS HOLLY

EXISTING BRADFORD PEAR

25

15

25

10

15

0

0

0

90

Revisions:

Job Number:

Drawing Name: PHASE 3 LANDSCAPE PLAN Drawing Number: